

24.4.17

**NAGAR NIGAM, GORAKHPUR**

Name of Work

सड़क को जो गल्ले/मुल्ले मिटे जाते हैं उस सड़क को जो गल्ले/मुल्ले मिटे जाते हैं उस सड़क को जो गल्ले/मुल्ले मिटे जाते हैं

Estimated Cost

Earnest Money Rs.

Rs 1000000 = 00

Due date of Tender

24.04.17

Name of Contractor Sri

Junior Engineer

Assistant Engineer

Executive Engineer

**BILL OF QUANTITY FOR ROAD WORK/DRAIN WORK**

Sl. No.	Particular	Qty.	Unit	Rate
1.	Dismantling old and damaged boe soil- ing i/c all the labour T&P etc. complete.	----	Per M <sup>2</sup> =	
1A	40-63 mm तथा 22-40-53 mm stone Ballast असुरे के साथ प्रीमिअ कार्पेट प्राति वर्ग मीटर			1150/70 Per m <sup>2</sup>
2.	Dismantling old and damaged B/work including stacking of material etc.	----	Per M <sup>3</sup> =	
2A	22-40 mm stone Ballast असुरे के साथ प्रीमिअ कार्पेट मीटर			860=90 Per m <sup>2</sup>
3/a.	E/W filling including cartage the earth upto 8.00 Km including ramming, dressing and leveling etc. complete.	----	Per M <sup>3</sup> =	
3/b.	Same as above but up to 4.00 Km.	----	Per M <sup>3</sup> =	
3/c	20% 22-40-53 क्लोस कार्पेट के साथ प्रीमिअ कार्पेट मीटर			365.10 per m <sup>2</sup>
4.	Laying the B.O.E. siling laid on edge with prescribed camber and slope with Sob Bricks.	----	Per M <sup>3</sup> =	
5.	Same as above item no. 3 but for flatsoling with Sob Bricks	----	Per M <sup>2</sup> =	

## Nagar Nigam Gorakhpur Analysis of Cost

40-63 एम०एम० तथा 22- 40 -53 mm Stone Ballast कुटाई के साथ प्रीमिक्स कार्पेट प्रति वर्ग.मी० की दर  
Area 1.0 m<sup>2</sup>

S.No.	Item Name	L (m)	B (m)	H (m)	Qty	Unit	Rate	Amount (Rs.)
1	S/Stacking of 40-63 mm Stone Ballast	1.0	1.0	0.12	0.12	Cum	2263.50	271.62
2	S/Stacking of 22-40 -53 mm Stone Ballast	1.0	1.0	0.10	0.10	Cum	2480.40	248.0
3	Stone dust 20% Qty item No. 1 and 2				0.044	Cum	2302.20	101.30
4	Consolidation of Stone Ballast. Same Qty item No. 01 and 2				0.22	Cum	177.00	38.94
5	Water Allowance				0.22	Cum	40.00	8.80
6	Brick Edging both side.	1.0	—	—	1.0	Rmt	170.00	170.00
7	20mm thick primix carpet	1.0	1.0	—	0.0	Sqm	219.00	219.00
8	6mm thick seal coat	1.0	1.0	—	0.0	Sqm	93.00	93.00
							<b>Total</b>	<b>1150.70</b>
							say	1150.70

P. Chaturvedi  
S. K. Singh  
S. K. Singh  
S. K. Singh  
S. K. Singh  
S. K. Singh  
S. K. Singh  
S. K. Singh

10/11/17  
8-6  
CL  
15/11/17

# Nagar Nigam Gorakhpur

## Analysis of Cost

एक लेयर 22- 40 -53 mm Stone Ballast कुटाई के साथ प्रीमिक्स कार्पेट प्रति वर्ग मी0 की दर  
Area 1.0 m2

S.No.	Item Name	L (m)	B (m)	H (m)	Qty	Unit	Rate	Amount (Rs.)
1	S/Stacking of 22-40 -53 mm Stone Ballast	1.0	1.0	0.12	0.12	Cum	2480.40	297.65
2	Stone dust 20% Qty item No. 1				0.024	Cum	2302.20	55.25
3	Consolidation of Stone Ballast. Same Qty item No. 01				0.12	Cum	177.00	21.24
4	Water Allowance				0.12	Cum	40.00	4.80
5	Brick Edging both side.	1.0	—	—	1.0	Rmt	170.00	170.00
6	20mm thick primix carpet	1.0	1.0	—	0.0	Sqm	219.00	219.00
7	6mm thick seal coat	1.0	1.0	—	0.0	Sqm	93.00	93.00
							Total	860.94
							say	860.90

*Handwritten:* 5/5  
ll  
Raddo

*Handwritten:* Pochho  
G.B.

*Handwritten:* Area  
10/11/17  
J-G

*Handwritten signature:* [Signature]

*Handwritten:* Pochho  
13.4.17  
EL

*Handwritten:* [Signature]  
13/4/17  
EE

*Handwritten:* [Signature]  
13/4/17

*Handwritten:* [Signature]  
15/4/17


# Nagar Nigam Gorakhpur

20% 22.4-53.0 mm स्टेन-  
बैलास्ट सहित  
प्रिमिक्स कार्पेट प्रति वर्ग मी० की दर

## Analysis of Cost

Area 1.0 m<sup>2</sup>

S.No.	Item Name	L (m)	B (m)	H (m)	Qty	Unit	Rate	Amount (Rs.)
1	S/Stacking of 22-40 -53 mm Stone Ballast 20% for patch area.	1.0	1.0	0.10	0.02	Cum	2480.40	49.61
2	Consolidation of Stone Ballast. Same Qty item No. 01				0.02	Cum	177.00	3.54
3	20mm thick primix carpet	1.0	1.0	-	1.0	Sqm	219.00	219.00
4	6mm thick seal coat	1.0	1.0	-	1.0	Sqm	93.00	93.00
							<b>Total</b>	<b>365.15</b>
							say	365.00

  
 S.E.  
 10/11/17  
 S.E.  
 13/4/17  
 S.E.  
 13/4/17  
 S.E.  
 15/4/17  
 S.E.

Note.

All the above work will be carried out as per P.W.D Detail Specification and to entire satisfaction of All

- 1- I/We deposited earnest money (Yes/No)
- 2- Details of deposited money is as under:-

Type of earest Money and No.	Issuing institute	Date of issue	Amount

3- I/We hereby agree to execute the above work at (in figure) \_\_\_\_\_ above/below  
 (in words) \_\_\_\_\_  
 or mentioned estimated rates.

4- I/We agree with terms and conditions and specification of work on Nagar Nigam Gorakhpur.

-----  
 Contractor

**(For Official Use)**

- 1- Rates area (a) in Figure ----- % above/below
- (b) in words ----- % above/below.
- 2- Cutting or overwriting No./Yes
- 3- E. M Attached No./Yes
- 4- Any other

**Assistant Engineer**

**Executive Engineer**